

# TABELA ROBÓT ZIEMNYCH

**Tabela robót ziemnych do projektu na  
przebudowę ul. Jagodowej w zakresie wykonania chodnika w Sadowej**

Pikietaż	Powierzchnia przekroju		Powierzchnia średnia		Odległość	Objętość		Zużycie na miejscu	Nadmiar objętości		Suma algebraiczna	
	W	N	W	N		W	N		W	N	W	N
	m2	m2	m2	m2		m3	m3		m3	m3	m3	m3
0 + 0,00	0,000	0,000									0,000	0,000
0 + 35,00	1,920	0,000	0,960	0,000	35,000	33,600	0,000	0,000	33,600	0,000	33,600	0,000
0 + 53,00	1,980	0,000	1,950	0,000	18,000	35,100	0,000	0,000	35,100	0,000	68,700	0,000
0 + 73,00	2,510	0,000	2,245	0,000	20,000	44,900	0,000	0,000	44,900	0,000	113,600	0,000
0 + 105,00	2,010	0,000	2,260	0,000	32,000	72,320	0,000	0,000	72,320	0,000	185,920	0,000
0 + 120,00	2,040	0,000	2,025	0,000	15,000	30,375	0,000	0,000	30,375	0,000	216,295	0,000
0 + 146,00	0,670	0,170	1,355	0,085	26,000	35,230	2,210	2,210	33,020	0,000	249,315	0,000
0 + 164,00	0,540	0,240	0,605	0,205	18,000	10,890	3,690	3,690	7,200	0,000	256,515	0,000
0 + 193,00	0,710	0,100	0,625	0,170	29,000	18,125	4,930	4,930	13,195	0,000	269,710	0,000
0 + 213,00	0,750	0,040	0,730	0,070	20,000	14,600	1,400	1,400	13,200	0,000	282,910	0,000
0 + 267,00	0,480	0,090	0,615	0,065	54,000	33,210	3,510	3,510	29,700	0,000	312,610	0,000
0 + 283,00	0,640	0,090	0,560	0,090	16,000	8,960	1,440	1,440	7,520	0,000	320,130	0,000
0 + 327,00	0,670	0,000	0,655	0,045	44,000	28,820	1,980	1,980	26,840	0,000	346,970	0,000
0 + 380,00	0,720	0,000	0,695	0,000	53,000	36,835	0,000	0,000	36,835	0,000	383,805	0,000
0 + 417,00	0,390	0,000	0,555	0,000	37,000	20,535	0,000	0,000	20,535	0,000	404,340	0,000
0 + 472,00	1,870	0,000	1,130	0,000	55,000	62,150	0,000	0,000	62,150	0,000	466,490	0,000
0 + 495,00	1,930	0,000	1,900	0,000	23,000	43,700	0,000	0,000	43,700	0,000	510,190	0,000
0 + 538,00	0,920	0,000	1,425	0,000	43,000	61,275	0,000	0,000	61,275	0,000	571,465	0,000
0 + 586,00	2,310	0,000	1,615	0,000	48,000	77,520	0,000	0,000	77,520	0,000	648,985	0,000
0 + 613,00	1,310	0,000	1,810	0,000	27,000	48,870	0,000	0,000	48,870	0,000	697,855	0,000
0 + 627,00	1,870	0,120	1,590	0,060	14,000	22,260	0,840	0,840	21,420	0,000	719,275	0,000
0 + 680,00	1,090	0,000	1,480	0,060	53,000	78,440	3,180	3,180	75,260	0,000	794,535	0,000
0 + 725,00	1,910	0,000	1,500	0,000	45,000	67,500	0,000	0,000	67,500	0,000	862,035	0,000
0 + 775,00	2,020	0,000	1,965	0,000	50,000	98,250	0,000	0,000	98,250	0,000	960,285	0,000
0 + 811,00	1,540	0,070	1,780	0,035	36,000	64,080	1,260	1,260	62,820	0,000	782,095	0,000
0 + 852,00	1,710	0,000	1,625	0,035	41,000	66,625	1,435	1,435	65,190	0,000	859,725	0,000

# TABELA ROBÓT ZIEMNYCH

0 + 873,00	1,850	0,000	1,780	0,000	21,000	37,380	0,000	0,000	37,380	0,000	819,475	0,000
------------	-------	-------	-------	-------	--------	--------	-------	-------	--------	-------	---------	-------

Sporządził:

**Krzysztof Bielawski**

1151,550	25,875	25,875	1125,675	0,000
A	B	C	D	E
B-A = E-D            25,875-1151,550= 0-1125,675				
A-D = B-E            1151,550-1125,675 = 25,875-0				